



NOTES

1. CONCRETE SHALL HAVE A MINIMUM BREAKING STRENGTH OF 3000 PSI. AFTER 28 DAYS, 6 SACK MIX.
2. CURB JOINT SHALL BE A TROWELED JOINT WITH A MIN. 1/2" RADIUS ALONG THE BACK OF CURB.
3. CONTRACTION JOINT SPACING SHALL NOT EXCEED 10 FEET AND SHALL BE CONSTRUCTED FLUSH.
4. USE EXISTING CURB EXPANSION JOINT OR SAW CUT AND PLACE COLD JOINT.
5. SPACING OF 2" CONCRETE SUPPORT BLOCKS SHALL BE NO GREATER THAN 3' AND BLOCKS SHALL BE TIED TO #4 REBAR WITH WIRE.
6. SIDEWALK THICKNESS SHALL BE 6 INCHES MINIMUM, REINFORCED, AND EXTEND TO AT LEAST ONE SIDEWALK PANEL

Detail Drawing may not be altered or changed in any manner except by the Public Works Director. It is the responsibility of the user to acquire the most current version.

**CITY OF MOLALLA
DEPARTMENT OF PUBLIC WORKS**

COMMERCIAL DRIVEWAY



DRAWN BY	PDG	04/2016
CHECKED BY	JC	04/2016

R-1095